
Machining Level-IV

Based on October 2023, curriculum version II



Module Title: - Supervise Working Drawing Module

Code: INDMAC4 M01 1023

TTLM Code: IND MAC4 TTLM01 1023-I

Nominal Duration: 60Hours

Prepared by: Ministry of Labor and Skill

October, 2023

Addis Ababa, Ethiopia

Acknowledgment

The Ministry of Labor and skill wishes to thank and appreciation to MoLS leaders and experts, Regional Labor and skill/training Bureaus leader, experts, TVT College Deans, Instructors and industry experts who contribute their time and professional experience to the development of this Training Module.

Acronym

AD	Auxiliary Dimensions
AMF	Additive Manufacturing File Format
C#	C Sharp
CAD	Computer-Aided Design
CAM	Computer-Aided Manufacturing
CATIA	Computer-Aided Three-Dimensional Interactive Application
CNC	Computer Numerical Control
DWF	Design Web Format
DWG	Drawing
DXF	(Drawing Exchange Format):
FD	Functional Dimension
HPGL	Hewlett-Packard Graphics Language
IFC	Industry Foundation Classes
IGES	Initial Graphics Exchange Specification
KPI	Key Performance Indicators
NFD	Non Functional Dimensions
OBJ	Wavefront Object
STEP	Standard for the Exchange of Product Data
STL	Stereo Lithography
VB.NET	Visual Basic dot Net
VBA	Visual Basic for Applications
Xrefs	References

Table of Contents

Acknowledgment 1
Acronym 2
Table of Contents 3
Introduction to the Module 4
Unit Two: Working Drawing Brief 5
1.1 Working drawing objectives, scope and parameters 6
1.2 Engineering detail drawings standards, codes and information 7
1.3 Consult resource requirement 14
Self-Check 1 18
Unit Two: Preliminary sketch/drawing/ specifications 21
1.1 Basic components, assemblies and fasteners 22
2.2 Project materials selection criteria 26
2.3 Drawing approving procedure 28
Self-check 2 30
Unit Three:-Lead detail drafting project 32
3.1. Project Work Plan and Parameters 33
3.2. CAD software platform and file formats 40
3.3. Drawing stockholders communication accuracy 48
Self-Check 3 50
Operation sheet 3.1 51
Operation sheet 3.2 52
Operation sheet 3.3 53
LAP Test ..... **Error! Bookmark not defined.**
Unit Four:- Monitor detail drafting outcomes 55
4.1. Progress Monitoring 56
4.2. Assisting drafting personnel 60
4.3. Drawing validations and documentation 61
4.4. 3-D models and detail drawings reviewing 63
4.5. Monitoring the presentation of drawings and project outcomes 65
Self-Check 3 66
References 69
Developer's Profile 70

Introduction to the Module

Production or working drawings are specialized engineering drawings that provide information required to make the part or assembly of the final design. Working drawings rely on orthographic projection and many other graphical techniques (sectioning, dimensioning, tolerancing, etc.) to communicate design information for production.

Working drawing supervision involves the oversight and management of the creation, review, and coordination of working drawings in various industries such as architecture, engineering, manufacturing, and construction. Working drawings provide detailed information about the construction, assembly, and installation of components and systems.

The primary goal of working drawing supervision is to ensure that the working drawings accurately represent the design intent and provide clear instructions for construction or fabrication. The supervisor, often a qualified professional such as an architect, engineer, or project manager, plays a crucial role in maintaining quality control, coordinating with stakeholders, and facilitating effective communication throughout the project.

Working drawing supervision plays a vital role in ensuring that construction or fabrication projects proceed according to the design intent, specifications, and industry standards. By overseeing the creation, review, and coordination of working drawings, the supervisor helps maintain quality, minimize errors, and facilitate effective communication among project stakeholders.

Unit Two: Working Drawing Brief

This learning unit is developed to provide the trainees the necessary information regarding the following content coverage and topics:

- Working drawing objectives, scope and parameters
- Engineering detail drawings standards, codes and information
- Consult resource requirement

This unit will also assist you to attain the learning outcomes stated in the cover page.

Specifically, upon completion of this learning guide, you will be able to:

- Understand working drawing objectives, scope and parameters
- Identify Engineering detail drawings standards, codes and information
- Consult project resource requirement

1.1 Working drawing objectives, scope and parameters

Working drawings are used to convey the design intent of the engineer or architect to the builder or contractor. They provide clear and concise instructions for the construction or fabrication of a product or structure. Working drawings typically include dimensions, tolerances, materials, specifications, construction details, assembly instructions, and a bill of materials.

Objectives

The objectives of working drawings are to:

Communicate the design intent of the engineer or architect to the builder or contractor.

Provide clear and concise instructions for the construction or fabrication of a product or structure.

Facilitate the coordination of different trades and disciplines involved in the project.

Serve as a permanent record of the design.

Scope

- Working drawings typically include the following information:
- Dimensions and tolerances
- Materials and specifications
- Construction details
- Assembly instructions
- Bill of materials

Parameters

The parameters of working drawings are defined by the specific project requirements and the applicable codes and standards. Some common parameters include:

- Drawing scale
- Line types and symbols
- Drawing format and layout
- Revision control

Examples

Working drawings are used in a wide variety of industries, including engineering, construction, manufacturing, and architecture. Here are a few examples of working drawings:

Engineering drawings: These drawings are used to communicate the design of technical products, such as machines, bridges, and electronic devices.

Construction drawings: These drawings are used to guide the construction of buildings and other structures.

Manufacturing drawings: These drawings are used to specify the dimensions and tolerances of manufactured parts and components.

Architectural drawings: These drawings are used to communicate the design of buildings and other structures




Figure 1.1 working drawing

1.2 Engineering detail drawings standards, codes and information

Engineering graphics is an effective way of communicating technical ideas and it is an essential tool in engineering design where most of the design process is graphically based. Engineering graphics is used in the design process for visualization, communication, and documentation. Graphics is a visual communications language that include images, text, and numeric information. Graphics communications using engineering drawings and models is a clear and precise language with definite rules that must be mastered in order to be successful in

engineering design. Graphics communications are used in every phase of engineering design starting from concept illustration all the way to the manufacturing phase.

An engineering (or technical) drawing is a graphical representation of a part, assembly, system, or structure and it can be produced using freehand, mechanical tools, or computer methods.

Working drawings are the set of technical drawings used during the manufacturing phase of a product. They contain all the information needed to manufacture and assemble a product.

Codes and Standards

Codes and standards are made to organize and unify the engineering work. Imagine; what if there was no standard for bolts?

- A code is a set of specifications for the analysis, design, manufacture, and construction of something.
- A standard is a set of specifications for parts, materials, or processes intended to achieve uniformity, efficiency and specific quality.

Examples of the organizations that establish standards and design codes: ISO , AISI, SAE, ASTM, ASME, ANSI, DIN.

Drawing Software

The most current version of CAD is preferred to be used, whilst earlier versions are acceptable. Earlier versions tend to have compatibility issues with later versions.

There are many different standards related to technical drawings.

The ISO standards for technical drawings are found in a two volumes handbook:

- ISO Standards Handbook: Technical drawings, Volume 1: Technical drawings in general
- ISO Standards Handbook: Technical drawings, Volume 2: Mechanical engineering drawings; Construction drawings; Drawing equipment

Drawing Units

All drawings will conform to SI units (Systems International). mm or inch

Language

All notes, comments and text will be in the English language (UK Standard). All instructions on a drawing shall be in the imperative tense i.e.: ducting to be insulated, 150mm high steel plinths to be provided for axial fans.

1.2.1 Information to be included on Shop Drawings

Shop drawings must make reference to the appropriate design drawings produced by the Engineer by indicating drawing number(s) and revision number(s) and the appropriate section of the specification.

1.2.1.1 Shop drawings must include the following information:

- The original date of issue
- The dates of all applicable revisions;
- The project title;
- Where applicable, the project address;
- The project number;
- Wherever applicable, the name(s) of the:
    - Contractor(s),
    - Sub-contractor(s),
    - Supplier(s),
    - Manufacturer(s), and
    - Separate detailer(s);
- The sequence number for each shop drawing;
- Identifications of all products and materials;
- Relation to adjacent structures or materials;
- Clearly-identified field dimensions; and
- Applicable standards – such as a By Laws, SANS, ASHRAE, ASIB, BS, EN, etc

When the manufacturer's standard schematic drawings, catalogue sheets, diagrams, schedules, performance charts, illustrations and other standard descriptive data are submitted as shop drawings, the contractor is to, where applicable:

a. Delete information which is not applicable to the project;

b. Supplement standard information where necessary to provide additional information applicable to the project;
c. Show dimensions and clearances required;
d. Show performance characteristics and capacities; and
e. Show wiring diagrams and controls.

1.2.1.2 Shop drawings provided for equipment must use the abbreviations used in the specifications from the Engineer and, where applicable, include the following:

- Manufacturer identification;
- Model number;
- Installation arrangement;
- Material sizes;
- Construction details;
- Dimensions;
- Weight;
- Operating characteristics as they relate to the use of application;
- Operating performance curves;
- IP Rating of equipment
- Performance curves with clearly-indicated performance range(s);
- Equipment efficiency;
- Duty cycles;
- Motor duty cycles;
- Electrical classification;
- Electrical data and characteristics;
- Electrical wiring schematics & control logic;
- Approvals;
- Sound levels; and
- Vibration levels if applicable.

The information above is typically available from the equipment manufacturer on request and is incumbent on the contractor to ensure this is presented to the

Engineer for approval. Failure to request for approval of deviation from specification contained in BoQ and/or Technical specification, and/or Project Drawings, and/or Standards (as per Point 4.1 above), shall not absolve the contractor of the requirement to comply and the costs to remedy such shall be borne by the contractor.

Drawing paper Sizes

STANDARD SIZE	DIMENSIONS	
Width (mm)	Width (mm)	Length (mm)
A4	210	297
A3	297	420
A2	420	594
A1	594	841
A0	841	1189

Figure 1: Standard "A" Series Drawing Sizes

Long drawings, where necessary for piping, wiring/circuit diagrams, cable run diagrams, etc. shall be prepared with widths equal to the widths of "A" series sheets, as required.

Drawing Scales

The requirements of scale settings are as follow:

When using model space, the design must always be full size, i.e. active scale = 1:1.

In the case of non-dimensional drawings such as diagrammatic drawings, the viewport must be scaled to suit the drawing sheet. Different vertical and horizontal scales may be chosen in order to exaggerate a profile or to clarify thin layers of a section.

PREFERRED SCALES		
1:1	1:2	1:5
1:10	1:20	1:25
1:100	1:200	1:50
1:1000	1:2000	1:500

Figure 2: Preferred Drawing Scales

Dimensioning

- All detailed dimensions shall be in millimeters and must be of the filled head arrow type.
- All notes must have a leader pointing at the detail referred to.
- Co-ordinates shall be stated in meters to 3 decimal places.

- Dimensioning must be done whilst in model space, and NOT in an **active** viewport. Dimensions are not to be exploded.

Title Block, The title block is normally placed in the bottom right of the drawing frame, and it should contain the following information:

- the name of the company or organization
- the title of the drawing
- the drawing number, which is generally a unique filing identifier
- the scale
- the drawing size
- the angle of projection used, either first or third, generally shown symbolically
- the signature or initials of the draftsman, checker, approving officer, and issuing officer, with the respective dates
- the material of the part
- the revision number
- the sheet number for multi-sheet drawings
- other information as required (tolerances, surface finish, etc.)

In addition to the information above, for drawings produced using CAD software, it is highly recommended to have the following information in the title block:

- the name of the CAD software used and its version
- the name of the drawing file
- the name of the source part or assembly file
- the units of the dimensions (if the drawing is mistakenly printed on a different paper size, the scale becomes meaningless)

Revision Table, A revision table is normally located in the upper right of the drawing frame. All modifications to the drawing should be documented there.

Material or Parts List (Bill of Materials), If the drawing contains a number of parts, or if it is an assembly drawing, a tabulated parts list is added to the drawing. The bill of materials is usually placed at the bottom right of the drawing frame, just above the title block.

The bill of materials should give the following information:

- the part number
- the part name
- the quantity required
- material specifications
- the drawing number of each individual part
- other applicable information

When the parts list is very large a separate drawing sheet may be used for the parts list alone.

Zoning, A drawing may be divided up into a grid using letters and numbers. When zoning is used it is located inside the drawing frame. Zoning is usually used for large size drawing sheets where it allows easy references to various parts of the drawing by referencing a coordinate such as B4.

Notes, Information other than pictorial views and dimensions necessary for completing a drawing is classified as "notes". Notes are usually placed in the lower left corner of the drawing sheet and they are numbered consecutively downward.

Some examples of the notes used in working drawings are as follows:

- Dimension Notes all dimensions apply after surface treatment.
- Heat Treating Notes heat treat in accordance with standard-XXX TO XXX-hardness
- Joining Method Notes (welding, brazing, etc.) Fusion weld in accordance with standard-XXX
- Plating and Coating Notes cadmium plate in accordance with standard XXX
- Surface Preparation Notes surface to be cleaned and polished for vacuum use.
- Testing and Inspection Notes radiographic inspection of all welds in accordance with standard-XXX
- Threaded Inserts — Cleaning and Installation Notes tightening torque of threaded fasteners should be as listed in torque table
- Miscellaneous Notes place in bag after final electro polishing.

1.3 Consult resource requirement

Project resource requirements refer to the various resources needed to successfully execute a project. These resources can be categorized into different types, including:

Human Resources: This encompasses the individuals with the necessary skills, expertise, and experience to carry out project tasks. It involves identifying the roles required, the number of people needed for each role, and their availability throughout the project's duration.

Physical Resources: These are the tangible assets required for project execution, such as equipment, tools, machinery, and physical workspace. It involves determining the specific types of equipment, their quantities, and the timing of their usage.

Financial Resources: This refers to the funding needed to cover project expenses, including salaries, material costs, equipment rentals, and other project-related expenditures. It involves creating a detailed budget that outlines the anticipated costs and ensures adequate financial resources are available.

Information Resources: This includes the data, documents, and knowledge required for informed decision-making and project execution. It involves identifying the necessary information sources, ensuring data accessibility, and establishing clear communication channels.

Time Resources: This refers to the time allocated for completing project tasks and achieving project objectives. It involves creating a project schedule that outlines task durations, dependencies, and milestones, ensuring realistic timelines are set.

To effectively consult project resource requirements, consider these steps:

Project Scope Definition: Clearly define the project's scope, objectives, and deliverables. This provides a framework for identifying the resources needed to achieve the desired outcomes.

Task Breakdown: Break down the project into smaller, manageable tasks. This allows for a more granular assessment of resource requirements for each task.

Resource Estimation: Estimate the quantity and type of resources needed for each task. Consider factors such as task complexity, skill requirements, and equipment needs.

Resource Availability: Check the availability of resources, including personnel schedules, equipment availability, and financial constraints.

Resource Allocation: Allocate resources to specific tasks, ensuring the right resources are assigned at the right time.

Resource Monitoring: Continuously monitor resource usage, identifying potential shortages or over allocations, and making adjustments as needed.

Effectively consulting project resource requirements ensures that the project has the necessary resources to achieve its objectives, maximizing efficiency and minimizing delays or cost overruns

To consult project resource requirements, you can follow these steps:

A. **Identify the project's goals and objectives.** What do you need to accomplish with the project? What are the deliverables?
B. **Break down the project into tasks.** What are the individual steps that need to be taken to complete the project?
C. **Estimate the resources required for each task.** This may include people, equipment, materials, and funding.
D. **Identify any constraints on the project.** This may include budget, time, and resources.
E. **Develop a resource plan.** This should include the following information:

- What resources are required?
- How much of each resource is required?
- When are the resources required?
- Who is responsible for managing each resource?

Once you have a resource plan, you can consult with stakeholders to ensure that the plan is feasible and achievable. You should also update the resource plan on a regular basis to ensure that it is up-to-date and reflects any changes to the project.

Here are some tips for consulting project resource requirements:


- Involve stakeholders early in the process. This will help to ensure that everyone is on the same page and that all of the necessary resources are identified.
- Be realistic about your estimates**.** It is better to overestimate the resources required than to underestimate them.
- Be flexible**.** Things don't always go according to plan, so be prepared to adjust the resource plan as needed.
- Communicate regularly with stakeholders**.** Keep them updated on the project's progress and any changes to the resource plan.

By following these steps, you can effectively consult project resource requirements and help to ensure the success of your project.

Standard Orthographic Projections

Two standards are commonly in use in orthographic projection of drawings; the First Angle Projection (European projection) and the Third Angle Projection (American projection). It should be noted that corresponding views are identical in both methods of projection except for their relative positions on the drawing paper.


The First Angle Projection



In here, the front view (A) is the basis (reference) and the other views are drawn as ‘shadows’ of that view. That is, the left hand side view for instance is drawn on the right side of the front view. Similarly, the top view (plan) is drawn at the bottom of the front view, etc.

The Third Angle Projection

Symbol:



Lines and Lettering

Lines

In Engineering Drawing, we make use of different lines and line styles to convey the desired message. These lines differ in (i) thickness and (ii) style. Typical uses of these lines are summarized below.

Type of Line and Designation	Applications	Recommended line thickness [mm] PAPER SIZE	
		A4/A3/A2	A1/A0
A: ——— A continuous thick line	1. Object line	0.5	0.7
B: ——— A continuous thin line	1. Dimensioning line 2. Projection or extension lines *(used to project points from one view to another)* 3. Hatching 4. Outlines of adjacent parts 5. Outline of revolved views or revolved sections 6. Leaders for notes 7. Imaginary outlines	0.25	0.35
C: ~~~ A continuous wavy line	1. Break line of part views and part sections when break lines are not center lines	0.25	0.35
D: - - - - - - - - A short thin dashes	1. Non-visible outline (hidden) *(3 – 4-mm strokes, 1 – 2-mm spaces)*	0.25	0.35

E: A thin chain line	1. Center lines and pitch circles 2. path lines for indicating movement and/or extreme positions 3. oulines positioned in front of a section 4. Folding edges in developments	0.25	0.35
F: A thin chain line with thick extremities	1. Cutting or viewing planes	0.5/0.25	0.7/0.35
G: A thick chain line	1. indication of surfaces with supplementary or different treatments	0.5	0.7

Self-Check 1

Instructions: answer all questions given below accordingly

- Given 25 minutes,
- Enumerate the following. Use a separate sheet of paper for answering.
- For Short answers, write the answer for the questions on the provided space.

Part I. Choose the Correct answer from the given alternatives

1. What is the primary objective of working drawings in engineering?

a) To communicate design intent

b) To showcase artistic skills

c) To estimate project costs

d) To provide entertainment

2. Which of the following is not an objective of engineering detail drawings?

a) To provide manufacturing instructions

b) To ensure compliance with safety regulations

c) To document project progress

d) To facilitate quality control

3. Which standard is commonly used for engineering detail drawings in the United States?

a) ISO 9001

b) ASME Y14.5

c) ANSI/IEEE Std 315

d) DIN 276

4. What is the purpose of project resource requirements in engineering?

a) To estimate project costs

b) To determine the necessary personnel and equipment

c) To define project milestones and timelines

d) To comply with environmental regulations

5.: Which of the following is not typically included in project resource requirements?

a) Material specifications

b) Labor requirements

c) Cost estimates

d) Project objectives

Part II. Say True if the statement is true or else say False

1. Working drawings are primarily used for aesthetic purposes in engineering projects.
2. Engineering detail drawings must adhere to specific industry standards to ensure consistency and clarity.
3. ASME Y14.5 is a widely recognized standard for engineering detail drawings in the United States.
4. Project resource requirements help in determining the necessary personnel, equipment, and materials for a project.

5. Project objectives are generally included in project resource requirements documentation.

Part III: - Give clear answer to the given questions bellow

1. Describe the importance of incorporating standardized symbols, conventions, and practices in working drawings.
2. Discuss the relationship between working drawings and other project documentation, such as specifications and bills of quantities.
3. Explain how working drawings can aid in the evaluation and selection of construction materials and components.
4. Discuss the importance of adhering to engineering detail drawing standards in the design and manufacturing processes.
5. Explain the role and significance of project requirement consultancy in the successful execution of engineering projects

Unit Two: Preliminary sketch/drawing/ specifications

This learning unit is developed to provide the trainees the necessary information regarding the following content coverage and topics:

- Basic components, assemblies and fasteners
- Project materials selection criteria
- Drawing approving procedure

This unit will also assist you to attain the learning outcomes stated in the cover page.

Specifically, upon completion of this learning guide, you will be able to:

- Identify Basic components, assemblies and fasteners
- Understand Project materials selection criteria
- Identify Drawing approving procedure

1.1 Basic components, assemblies and fasteners

Working drawings typically consist of several key components that provide detailed information about the construction, assembly, or fabrication of a project. These components vary depending on the specific discipline and project requirements. Here are some common components found in working drawings:

Sectioning

For complex components with a number of hidden details, external views may not be enough to enable machining of such components. In such cases, sectioning is recommended. Sectioning is achieved by assuming an imaginary cutting/sectioning plane (or several planes) passing through the detail of interest. The "cut section", as it would appear, is drawn. The position of the cutting plane is indicated by a thin, long chain, line with thick extremities. This chain line is labeled with capital letters with the direction of viewing indicated by arrows. The capital letters are
placed behind the arrows in the direction of viewing. The layout of sections and the designation/naming of sectional views is the same as for the corresponding ordinary external views.




Figure 2.1 section view

Dimensioning

To enable productions of machine parts/components, all the relevant dimensions have to appear on the drawing. The practice is that any dimension is shown only once in that view in which it appears more explicitly. For this reason, it is not surprising that most of the important dimensions appear in the front view. Repetitions are discouraged unless clarity necessitates this. To keep the drawing clean, it is advised to put all the dimensions outside the drawing, except where and when this is unavoidable.

There are three types of dimensions; Functional Dimensions (FD), Non-Functional Dimensions (NFD) and Auxiliary Dimensions (AD)




Figure 2.2. dimensioning

Threaded Parts

Threads are machined according to different standards. However, the trend nowadays is to machine threads (and other standard features) according to ISO standards. A letter “M” followed by a number designates the size of the threads. The “M” stands for metric and the number that follows thereafter indicates the diameter (in mm) of the shaft upon which the threads have been machined. Male threads (e.g. on a bolt) and female threads (e.g. on a nut) of the same size are designated by the same M number. This number actually specifies not only the size of the threaded part but also the size of the bolt head and the size of the nut (if all are made in accordance to the ISO standard). NOTE that by specifying the thread size (the M-number) automatically covers such details as; the nominal diameter, the pitch, the pitch diameter, the minor diameter, the major diameter, the various radii etc.




Figure 2.3. thread features

Machines Holes (Drilled and Milled holes)

Drilled Holes

Drilled holes are distinguished from holes machined by other methods by their characteristic tapered end. The shape of the drill bit brings about the tapered end.




Figure.2.4. drill hole

Milled Holes

Unlike drilled holes, milled holes have a flat end.




Figure.2.5. milled hole

Chamfers and Countersinks

At the end of each shaft or any drilled/machined hole, a small tapered end is machined just to eliminate the sharp edge. This is important because

• The sharp edge may hurt people during handling and/or on assembling

• The sharp edge wears and tears fast




Figure.2.6. Chamfers and Countersinks

Specially Treated Surfaces

If the surface demands special treatments (e.g. to be covered by wear resistance material, special lacquer etc), this has to be shown on the drawing. This is indicated on the drawing as follows:




Figure.2.7. special treated surface

Tolerances and Fits

- Tolerance is simply defined as “the degree (extent) of acceptable inaccuracy”
- It describes dimensional accuracy/inaccuracy
- Tolerance is necessary under mass production
- Absolute size (nominal size) is only theoretical/hypothetical
- Tolerance specifies the acceptable upper and lower limits for a given nominal size
- Usually two extreme conditions are of interest: tight fit and loose fit

2.2 Project materials selection criteria

The selection of project materials is a critical decision that impacts the performance, durability, aesthetics, and cost of a project. The criteria for selecting materials can vary depending on the specific project requirements, design intent, and budget. While the given drawing may not provide explicit material specifications, here are some general criteria that can guide material selection:

A. Functional Requirements: Consider the functional requirements of the project, such as load-bearing capacity, structural stability, insulation, fire resistance, moisture resistance, and durability. Choose materials that meet or exceed these requirements to ensure the project's performance and longevity.
B. Aesthetic Considerations: Evaluate the desired aesthetic qualities and architectural style reflected in the drawing. Consider the color, texture, finish, and visual appeal of

materials to achieve the desired look and feel. Ensure that the selected materials complement the overall design concept and create the desired visual impact.

C. Sustainability and Environmental Impact: Assess the environmental impact of materials and prioritize sustainable options. Look for materials that are recyclable, locally sourced, renewable, energy-efficient, or have low embodied carbon. Consider certifications such as LEED (Leadership in Energy and Environmental Design) ratings or eco-labels to guide sustainable material choices.
D. Cost and Budget: Evaluate the cost-effectiveness of materials and consider the project budget. Balance the desired quality, performance, and aesthetics with the available budget. Explore different material options, including alternatives that offer comparable qualities at a lower cost.
E. Availability and Lead Time: Consider the availability and lead time of materials. Ensure that the selected materials can be readily sourced and delivered within the project timeline. Evaluate the supply chain and potential risks associated with material availability, especially for specialty or custom materials.
F. Maintenance and Life Cycle Costs: Assess the maintenance requirements and life cycle costs of materials. Consider factors such as ease of cleaning, resistance to wear and tear, and longevity. Select materials that offer low maintenance requirements and long-term cost-effectiveness.
G. Compatibility and Integration: Evaluate the compatibility of materials with other project components, systems, and finishes. Ensure that selected materials can be seamlessly integrated with existing or planned elements without compromising functionality or aesthetics. Consider factors such as expansion and contraction rates, compatibility of joining methods, and interface details.
H. Regulatory and Code Compliance: Ensure that selected materials comply with relevant building codes, regulations, and industry standards. Consider factors such as fire ratings, acoustic properties, and accessibility requirements to meet the necessary compliance standards.

It's important to note that the specific material selection should be based on a comprehensive evaluation of these criteria in conjunction with the project's unique requirements, design

intent, and professional expertise. Consulting with architects, engineers, material suppliers, and other experts can provide valuable insights and help make informed material selection decisions.

2.3 Drawing approving procedure

The drawing approving procedure, also known as the drawing approval process, is a systematic method for reviewing, evaluating, and approving drawings before they are implemented in a construction or fabrication project. This process ensures that the drawings meet the required standards, comply with regulations, and accurately represent the design intent. While the specific steps and stakeholders involved may vary depending on the project and organization, here is a general outline of the drawing approving procedure:

I. Preparation of Drawings: The design team, which may include architects, engineers, and other relevant professionals, prepares the drawings according to the project requirements and design intent. The drawings are typically developed using Computer-Aided Design (CAD) software.
II. Internal Review: The drawings undergo an internal review within the design team or organization. This review involves a comprehensive evaluation of the drawings for accuracy, completeness, compliance with regulations, and adherence to project specifications. Each discipline may review their respective drawings to ensure coordination and compatibility with other disciplines.
III. Revision and Iteration: Based on the internal review, any necessary revisions or corrections are made to the drawings. This iterative process continues until the drawings are deemed satisfactory and ready for external review.
IV. External Review: The drawings are submitted to external stakeholders for review and approval. These stakeholders may include clients, regulatory authorities, consultants, or other relevant parties involved in the project. The external review ensures that the drawings meet the project requirements, comply with applicable regulations, and align with the client's expectations.
V. Review and Comment Resolution: The external stakeholders review the drawings and provide comments, suggestions, or requests for clarification. The design team

addresses these comments and resolves any issues or discrepancies. This iterative process continues until all comments are satisfactorily addressed.

VI. Approval and Sign-Off: Once all comments have been resolved, the final approved drawings are prepared. The stakeholders involved in the approval process, such as clients or regulatory authorities, provide their formal approval or sign-off on the drawings. This signifies their acceptance of the drawings and their readiness for implementation.

VII. Distribution and Implementation: The approved drawings are distributed to the relevant parties involved in the project, such as contractors, subcontractors, fabricators, or other stakeholders. These parties use the approved drawings as a reference for the construction, assembly, or fabrication process.

It's important to note that the specific steps and stakeholders involved in the drawing approval process can vary depending on the project's complexity, organizational structure, and contractual arrangements. Some projects may require multiple levels of approval or involve additional review bodies or consultants. Effective communication, coordination, and documentation throughout the drawing approval process are crucial to ensure that all stakeholders are aligned and that the project progresses smoothly.

Self-check 2

Part I. Choose the Correct answer from the given alternatives

1. Which of the following is a basic component of a working drawing?

a) Title block

b) Gantt chart

c) Risk assessment

d) Cost estimate

2. Which component of a working drawing provides information about the size and shape of the object being represented?

a) Section view

b) Bill of materials

c) Detail view

d) Scale

3. Which of the following is not a commonly used material selection criterion for engineering projects?

a) Cost

b) Aesthetics

c) Strength

d) Availability

4. Which step in the drawing approving procedure involves reviewing the technical accuracy and compliance of the drawing with design specifications?

a) Drawing submission

b) Drawing revision

c) Drawing approval

d) Drawing release

Part II. Say True if the statement is true or else say False

1. The title block in a working drawing provides information about the drawing's scale, author, and revision history.

2. Project material selection criteria may vary depending on factors such as project requirements, environmental considerations, and industry standards.

3. The drawing approving procedure typically involves multiple stakeholders, including design engineers, project managers, and quality control personnel.

4.: Drawing revision is a step in the drawing approving procedure that involves making changes to the drawing based on feedback or modifications.

5. The bill of materials is a component of a working drawing that lists all the materials and components required to build or assemble the object.

Part III: - Give clear answer to the given questions bellow

1. Discuss the importance of the title block as a basic component of a working drawing. What information should be included in the title block, and how does it enhance the clarity and organization of the drawing?

2. Explain the role of various views (such as sectional views, detail views, or isometric views) as components of a working drawing.

3. Discuss the key criteria that are typically considered when selecting materials for engineering projects.

4. Describe the process of material selection for a specific engineering project.

5. Explain the importance of the drawing approving procedure in ensuring the accuracy and quality of engineering drawings.

Unit Three:-Lead detail drafting project

This unit is developed to provide you the necessary information regarding the following content coverage and topics:

- Project Work Plan and Parameters
- CAD software platform and file formats
- Drawing stockholders communication accuracy

This unit will also assist you to attain the learning outcomes stated in the cover page. Specifically, upon completion of this learning guide, you will be able to:

- Confirm Project Work Plan and Parameters
- Identify CAD software platform and file formats
- Check Drawing information accuracy

3.1. Project Work Plan and Parameters

3.1.1. Project Work Plan

A project plan is a document that maps out the tasks, effort, timing, and resources needed to meet project goals within a predefined scope. It's often presented in the form of a Gantt-chart because it's easy to visualize the project timeline and ensure work stays on track.

A project work plan outlines the tasks, activities, timelines, and resources required to complete a project successfully.

Be sure to include the following components in any project plan you create:

- **Project tasks**: A detailed list of work to be done organized by project phase, process step, or work group
- **Project schedule**: A visual timeline of task start dates, durations, and deadlines, with clear progress indicators
- **Key milestones**: Major events, dates, decisions, and deliverables used for tracking forward progress
- **Dependencies**: A line connecting tasks that need to happen in a certain order
- **Resources**: Assignments that indicate the person or team responsible for completing a task

3.1.2. Resource Planning

Resources are people, equipment, place, money, or anything else that you need in order to do all of the activities that you planned for. Every activity in your activity list needs to have resources assigned to it. Before you can assign resources to your project, you need to know their availability. Resource availability includes information about what resources you can use on your project, when they're available to you, and the conditions of their availability. Don't forget that some resources, like consultants or training rooms, have to be scheduled in advance, and they might only be available at certain times. You'll need to know this before you can finish planning your project. If you are starting to plan in January, a June wedding is harder to plan than one in December, because the wedding halls are all booked up in advance. That is clearly a resource constraint. You'll also need the activity list that you created earlier, and you'll need to know how your organization typically handles resources. Once you've got a handle on these things, you're set for resource estimation.

3.1.3. Estimating the Resources

The goal of activity resource estimating is to assign resources to each activity in the activity list. There are five tools and techniques for estimating activity resources.

Expert judgment means bringing in experts who have done this sort of work before and getting their opinions on what resources are needed.

Alternative analysis means considering several different options for how you assign resources. This includes varying the number of resources as well as the kind of resources you use. Many times, there's more than one way to accomplish an activity and alternative analysis helps decide among the possibilities.

Published estimating data is something that project managers in a lot of industries use to help them figure out how many resources they need. They rely on articles, books, journals, and periodicals that collect, analyze, and publish data from other people's projects.

Project management software such as Microsoft Project, CAD software will often have features designed to help project managers estimate resource needs and constraints and find the best combination of assignments for the project.

Bottom-up estimating:- means breaking down complex activities into pieces and working out the resource assignments for each piece. It is a process of estimating individual activity resource need or cost and then adding these up together to come up with a total estimate. Bottom-up estimating is a very accurate means of estimating, provided the estimates at the schedule activity level are accurate. However, it takes a considerable amount of time to perform bottom-up estimating because every activity must be assessed and estimated accurately to be included in the bottom-up calculation. The smaller and more detailed the activity, the greater the accuracy and cost of this technique.

3.1.4. Estimating Activity Durations

Once you're done with activity resource estimating, you've got everything you need to figure out how long each activity will take. That's done in a process called activity duration estimating. This is where you look at each activity in the activity list, consider its scope and resources, and estimate how long it will take to perform.

Estimating the duration of an activity means starting with the information you have about that activity and the resources that are assigned to it, and then working with the project team to

come up with an estimate. You'll use these five tools and techniques to create the most accurate estimates:

Expert judgment will come from your project team members who are familiar with the work that has to be done. If you don't get their opinion, there's a huge risk that your estimates will be wrong.

Analogous estimating is when you look at similar activities from previous projects and how long they took. This only works if the activities and resources are similar.

Parametric estimating means plugging data about your project/drawing into a formula, ,CAD software, spreadsheet, database, or computer program that comes up with an estimate. The software or formula that you use for parametric estimating is based on a database of actual durations from past projects.

Three-point estimating is when you come up with three numbers: a realistic estimate that's most likely to occur, an optimistic one that represents the best-case scenario, and a pessimistic one that represents the worst-case scenario. The final estimate is the weighted average of the three.

Reserve analysis means adding extra time to the schedule (called a *contingency reserve* or a *buffer*) to account for extra risk.

Project Work Plan – Sample Template

NOTE : Applicants requesting funding for a multi-year grant program are REQUIRED to provide a Project Work Plan for EACH potential year of grant funding requested.

Goal:
Measurable Outcome(s):

*** Time Frame** (Start/End Dates by Month in Project Cycle)

Major Objectives	Key Tasks	Lead Person	1*	2*	3*	4*	5*	6*	7*	8*	9*	10*	11*	12*
1.														
2.														

Figure 3.1: project Work Plan template

3.1.5. The Project Life Cycle (Phases)

The project manager and project team have one shared goal: to carry out the work of the project for the purpose of meeting the project's objectives. Every project has a beginning, a middle period during which activities move the project toward completion, and an ending (either successful or unsuccessful). A standard project typically has the following four major phases: initiation, planning, implementation, and closure. Taken together, these phases represent the path a project takes from the beginning to its end and are generally referred to as the project "life cycle."

3.1.6. Project Schedule and Critical Path

The project schedule should be approved and signed-off by stakeholders and functional managers. This ensures they have read the schedule, understand the dates and resource commitments, and will cooperate. You'll also need to obtain confirmation that resources will be available as outlined in the schedule. The schedule cannot be finalized until you receive approval and commitment for the resource assignments outlined in it. Once the schedule is approved, it will become your baseline for the remainder of the project. Project progress and task completion will be monitored and tracked against the project schedule to determine if the project is on course as planned.

The schedule can be displayed in a variety of ways, some of which are variations of what you have already seen. Project schedule network diagrams will work as schedule diagrams when you add the start and finish dates to each activity. These diagrams usually show the activity dependencies and critical path.

The critical path method is an important tool for keeping your projects on track. Every network diagram has something that is called the critical path. It's the string of activities that, if you add up all of the durations, is longer than any other path through the network. It usually starts with the first activity in the network and usually ends with the last one.

Step 1. Start with a network diagram.




Figure 3.2: Step 1. Create a Network Diagram

Step 2. Find all the paths in the diagram. A path is any string of activities that goes from the start of the project to the end.


- Start > Activity "A" > Activity "B" > Finish
- Start > Activity "A" > Activity "C" > Finish
- Start > Activity "D" > Activity "E" > Finish

Step 3. Find the duration of each path by adding up the durations of each of the activities on the path.

- Start > Activity "A" > Activity "B" > Finish = 4 + 7 = 11
- Start > Activity "A" > Activity "C" > Finish = 4 + 2 = 6
- Start > Activity "D" > Activity "E" > Finish = 3 + 5 = 8

Step 4. The first path has a duration of 11, which is longer than the other paths, so it's the critical path.

The schedule can also be displayed using a Gantt chart (Figure 11.3).



	Task Name	Duration	Start	Finish
1	Design Server database structure	2 days	Sat 4/7/01	Sun 4/8/01
2	Implement Database Module	6 days	Mon 4/9/01	Sat 4/14/01
3	Implement Database Utility Module	4 days	Sun 4/15/01	Wed 4/18/01
4	Implement SuperUserManager Module	2 days	Thu 4/19/01	Fri 4/20/01
5	Implement I/O modules	7 days	Sun 4/8/01	Sat 4/14/01
6	Research RMILite and Ninja	4 days	Sun 4/15/01	Wed 4/18/01
7	Design Palm database structure	10 days	Thu 4/19/01	Sat 4/28/01
8	Implement Meeting Module	2 days	Mon 4/9/01	Tue 4/10/01
9	Implement Meeting Manager Module	2 days	Wed 4/11/01	Thu 4/12/01
10	Implement Open Meeting Monitor module	3 days	Fri 4/13/01	Sun 4/15/01
11	Implement Schedule Module	3 days	Wed 4/18/01	Fri 4/20/01
12	Implement Composite Schedule Module	4 days	Sat 4/21/01	Tue 4/24/01
13	Implement Authentication Manager Module	1 day	Thu 4/26/01	Thu 4/26/01
14	Implement Log Manager Module	1 day	Fri 4/27/01	Fri 4/27/01
15	Research OSKI	1 day	Sat 4/7/01	Sat 4/7/01
16	Implement User Synchronization Module	9 days	Sun 4/8/01	Mon 4/16/01
17	Implement Server Synchronization Module	9 days	Wed 4/18/01	Thu 4/26/01
18	Implement PalmOS GUI screen modules	9 days	Sat 4/7/01	Sun 4/15/01
19	Implement Client Rendezvous Application Module	4 days	Thu 4/19/01	Sun 4/22/01
20	Implement UI Manager Module	3 days	Mon 4/23/01	Wed 4/25/01
21	Design Intergration Tests	7 days	Tue 4/24/01	Mon 4/30/01
22	Intergration Testing	7 days	Tue 5/1/01	Mon 5/7/01
23	Blackbox Testing	3 days	Tue 5/8/01	Thu 5/10/01
24	User Testing	1 day	Fri 5/11/01	Fri 5/11/01
25	User Manual	1 day	Sat 5/12/01	Sat 5/12/01
26	Presentation Preperation	1 day	Mon 5/14/01	Mon 5/14/01

Figure 3.3: Gant-Chart

3.1.7. Project Parameters

Project parameters define the scope, budget, schedule, and quality of the project. There is an interrelationship among these parameters. If you choose to increase the scope, you must also increase the schedule or budget.

Project Parameters Process

Each client we have the privilege to work with is walked through the same design process. We'd like to share that with you step-by-step, starting with the project parameters.

Initial contact

Set up a time to meet.

Create a design proposal.

- Project parameters
- Conceptual design
- Construction documentation
- Construction consultation

Measure the existing structure.

Project parameters for working drawing preparation can include:

Budget: Total allocated budget and any financial constraints.

Resources: Availability and allocation of human, financial, and material resources.

Communication: Channels and frequency of project communication.

Reporting: Reporting structure, frequency, and formats.

Change Management: Process for handling change requests and approvals.

Project Scope:- Clearly define the scope of the working drawing project, including the specific components, structures, or systems to be documented. Identify any constraints, such as budget, timeline, or regulatory requirements. Timeline define the Start and end dates of the project

Deliverables:- Specify the expected deliverables, such as detailed working drawings, plans, elevations, sections, and schedules. Define the required formats and file types for the deliverables.

Standards and Guidelines: - Identify the relevant standards, codes, and guidelines that must be followed in the preparation of working drawings. Ensure compliance with industry-specific requirements and regulations.

Level of Detail:- Determine the required level of detail for the working drawings, considering the purpose and use of the drawings. Specify the level of accuracy, dimensions, and annotations needed.

Software and Tools:- Specify the CAD software or drafting tools to be used for creating the working drawings. Consider any specific software requirements or compatibility with other project stakeholders.

Drawing Organization:- Define the organization and structure of the working drawings, including sheet layout, title blocks, and numbering conventions. Specify the information to be included in the drawings, such as notes, legends, and symbols.

Drawing Coordination: Determine the coordination requirements with other disciplines or trades involved in the project. Establish communication channels and protocols for resolving clashes or conflicts.

Revision Control:- Establish a system for managing revisions and versions of the working drawings. Define the process for documenting and communicating revisions to stakeholders.

Quality Assurance:- Establish quality control measures to ensure accuracy, completeness, and compliance of the working drawings. Define review procedures, including peer reviews or third-party inspections. Quality Standards: Specific quality criteria and standards to be followed.

Project Team: Identify the roles and responsibilities of team members involved in the working drawing preparation, such as architects, engineers, drafters, and consultants. Define coordination and collaboration protocols among team members.

Project Schedule:- Develop a timeline and schedule for the preparation of working drawings, taking into account dependencies and milestones. Establish deadlines for key deliverables and review cycles.

Communication and Reporting: Define communication channels and frequency for project updates, coordination meetings, and progress reports. Identify key stakeholders and their roles in the review and approval process.

Documentation and Archiving: Establish procedures for documenting and archiving the working drawings and associated project files. Specify file naming conventions and storage locations.

Risk Management: Identify potential risks or challenges that may impact the preparation of working drawings. Develop mitigation strategies and contingency plans to address these risks. Risks and Mitigation: Identified project risks and mitigation strategies.

3.2. CAD software platform and file formats

CAD (Computer-Aided Design) software platforms are widely used for creating and editing digital drawings and models. Here are some commonly used CAD software platforms:

AutoCAD: AutoCAD, developed by Autodesk, is one of the most popular CAD software platforms. It offers a comprehensive set of tools for 2D drafting and 3D modeling.

SolidWorks: SolidWorks, developed by Dassault Systems, is primarily used for mechanical design and engineering. It offers parametric modeling capabilities and tools for creating assembly designs.

Fusion 360: Fusion 360, developed by Autodesk, is a cloud-based CAD/CAM software platform that combines design, engineering, and manufacturing capabilities.

These are just a few examples of CAD software platforms available in the market. Each software platform has its own features, capabilities, and compatibility with different file formats.

Regarding file formats, CAD software typically supports both proprietary formats specific to the software platform itself and standard file formats that can be used across multiple CAD software. Some commonly used file formats in CAD include:

- **DWG (Drawing**): This is the native file format used by AutoCAD and is widely supported by many CAD applications.
- **DXF (Drawing Exchange Format):** DXF is a file format that allows for the exchange of CAD data between different software platforms. It is widely supported and can be used to share drawings between various CAD software.
- **DWF (Design Web Format):** DWF is a file format used for sharing and publishing CAD drawings in a lightweight and secure format. It allows for easy viewing and printing of CAD drawings without the need for the original CAD software.
- **IFC (Industry Foundation Classes):** IFC is an open file format used in BIM to exchange data between different software platforms. It allows for the interoperability of BIM models and facilitates collaboration among project stakeholders.
- **STL (STereoLithography):** STL is a file format commonly used for 3D printing. It represents the surface geometry of a 3D model using triangles.
- **STEP (Standard for the Exchange of Product Data):** STEP is a standardized file format used for exchanging 3D models across different CAD software platforms. It supports both geometry and product data.
- The **Initial Graphics Exchange Specification (IGES)** is a file format used for the exchange of 2D and 3D CAD data between different computer-aided design (CAD) systems. It was developed in the late 1970s as an industry-standard format to address the issue of interoperability between various CAD software platforms. IGES files contain a standardized representation of geometric and non-geometric data, enabling the transfer of CAD models, including solid models, wireframes, surfaces, and assembly structures. The format is based on a neutral, vendor-neutral, and platform-independent representation of CAD data.

- CATIA (Computer-Aided Three-Dimensional Interactive Application) is a comprehensive software suite developed by Dassault Systèmes. It is widely used in various industries, including aerospace, automotive, industrial design, and engineering. CATIA provides a versatile platform for design, analysis, simulation, and manufacturing of products.

3.2.1. Customising CAD Software system

AutoCAD, SolidWorks, and CATIA are powerful software systems that offer customization options to tailor the software to specific user requirements and workflows. Here are some ways you can customize these software systems:

AutoCAD Customization:

AutoCAD can be customized and tailored for use in machining applications to enhance productivity and streamline the manufacturing process.

Here are some ways to customize AutoCAD for machining:

Custom Tool Libraries:

- Create a library of tools, including end mills, drills, taps, and other cutting tools commonly used in machining.
- Model the physical representation of each tool as a block or symbol in AutoCAD.
- Assign attributes to the tool blocks, such as diameter, length, flute count, and tool number, to facilitate tool selection and documentation.

Custom Drawing Templates:

- Develop custom drawing templates that conform to your machining standards and requirements.
- Customize title blocks, borders, and annotations to include essential information, such as part numbers, material specifications, and machining notes.
- Predefine layers and linetypes specific to machining operations for ease of use and consistency.

Parametric Design:

- Utilize AutoCAD's parametric design capabilities to create models with adjustable dimensions and parameters.

- Design parts with proper tolerances and incorporate design-for-manufacturing principles, considering machining requirements and constraints.

CAD-to-CAM Workflow:

- Customize your AutoCAD models for seamless integration with Computer-Aided Manufacturing (CAM) software.
- Ensure that your AutoCAD models contain the necessary geometry, such as closed profiles and accurate dimensions, required for generating toolpaths in CAM software.

Custom LISP or VBA Programs:

- Leverage AutoLISP or VBA programming capabilities in AutoCAD to automate repetitive tasks and create custom commands for machining workflows.
- Develop scripts or programs that automate processes like generating toolpaths, creating machining features, or performing calculations specific to your machining requirements.

Custom Hatch Patterns:

- Create custom hatch patterns in AutoCAD to represent different machining operations, such as drilling, milling, or turning.
- Customize the appearance, spacing, and scale of hatch patterns to match your machining standards and preferences.

External References (Xrefs):

- Utilize Xrefs in AutoCAD to reference external drawings or models that contain machining-specific details, such as fixtures, jigs, or tooling layouts.
- Xrefs allow you to maintain separate files for different aspects of the machining process while ensuring consistency and coordination across the design.
- Collaboration and Documentation:
- Use AutoCAD's collaboration and documentation features to communicate machining instructions and requirements effectively.
- Utilize markup tools, revision clouds, and text annotations to highlight specific machining details or changes.
- Generate accurate 2D drawings, assembly views, and sections to provide clear and comprehensive instructions to machinists.

SolidWorks Customization:

SolidWorks API: SolidWorks supports the use of its Application Programming Interface (API) to create custom add-ins, macros, and automation scripts. You can use programming languages such as Visual Basic for Applications (VBA), C#, or VB.NET to extend the functionality of SolidWorks and automate repetitive tasks.

Custom Features and Templates: SolidWorks allows you to create custom features, such as parts, assemblies, and drawings, tailored to specific design requirements. You can also create custom templates for various design disciplines, standardizing your project settings and reducing setup time.

SolidWorks can be customized and integrated with CNC (Computer Numerical Control) machines to streamline the manufacturing process. Here are some ways you can customize SolidWorks for CNC machines:

CAM (Computer-Aided Manufacturing) Integration:

- SolidWorks offers CAM solutions, such as SolidWorks CAM and CAMWorks, which integrate directly within the software.
- CAM software allows you to generate toolpaths, define machining operations, and generate G-code for CNC machines directly from your SolidWorks models.
- Customize CAM settings and strategies to optimize toolpaths, cutting parameters, and machining operations specific to your CNC machine capabilities.

CAD-to-CAM Workflow:

- Customize your SolidWorks models and assemblies to be CNC-ready by incorporating design considerations for manufacturing.
- Design parts with proper tolerances, consider tooling requirements, and ensure manufacturability.
- Utilize SolidWorks features such as Draft Analysis, Thickness Analysis, and Check Geometry to validate part geometry for CNC machining.

CNC Machine Libraries:

- Create and maintain a library of CNC machine models within SolidWorks.
- Model the physical representation of your CNC machines, including the machine bed, workholding fixtures, tool holders, and tooling.

- Associate the appropriate CNC machine model with your SolidWorks parts or assemblies to ensure accurate visualization and clash detection during the design process.

G-code Simulation:

- Use SolidWorks add-ins or third-party software to simulate the G-code generated by your CAM software.
- G-code simulation allows you to visualize the toolpaths and machining operations in a virtual environment, verifying the accuracy and collision-free nature of the CNC program.
- Identify any potential issues, such as tool interference, collisions, or errors, before running the program on the CNC machine.

Custom Post-Processors:

- Post-processors are software components that convert CAM-generated toolpaths into machine-specific G-code.
- Customize or create post-processors specific to your CNC machines to ensure compatibility and optimize the generated G-code.
- Post-processors define machine-specific commands, tool change sequences, feed rates, and other parameters required by your CNC machine controller.

CNC Documentation:

- Generate manufacturing documentation, such as setup sheets, tool lists, and work instructions, directly from your SolidWorks models.
- Customize drawing templates and utilize SolidWorks annotation tools to create clear and detailed documentation for CNC operators.
- Include dimensions, tolerances, machining instructions, and part images to aid in the CNC machining process.

Training and Support:

- SolidWorks provides training resources, tutorials, and user communities to help you learn and master the tools and workflows related to CNC customization.
- Explore SolidWorks certified training courses, online forums, and support resources to expand your knowledge and skills in utilizing SolidWorks for CNC machining.

3.2.2. Organizational files, library, templates and symbols

Organizing files, creating libraries, templates, and using symbols are essential for maintaining a structured and efficient workflow in CAD software. Here's a guide on how to effectively manage these elements:

File Organization:

- Establish a well-structured folder hierarchy on your computer or network drive to store CAD files.
- Create main folders for different projects or clients and subfolders for specific file types (e.g., drawings, models, templates, etc.).
- Use descriptive names for files and folders to facilitate easy searching and identification.

Libraries:

- Create libraries to store commonly used CAD components, such as blocks, layers, styles, or hatch patterns.
- Identify and categorize components based on their type or function (e.g., electrical symbols, furniture blocks, construction details, etc.).
- Maintain consistent naming conventions and proper documentation to ensure library items are easily accessible and understandable.

Templates:

- Develop customized drawing templates to standardize and streamline the creation of new CAD files.
- Include essential elements in the template, such as title blocks, borders, company logos, standard layers, text styles, and dimension styles.
- Define appropriate units, scales, and tolerances based on your project requirements.
- Save the template file in a designated location for easy access when starting new projects.

Symbol Libraries:

- Create symbol libraries to store frequently used symbols or components specific to your industry or discipline.

- Symbols can include electrical symbols, mechanical parts, architectural elements, or any other commonly used graphic representations.
- Organize symbols into categories or folders within the library for easy navigation and retrieval.
- Ensure that symbols are accurately scaled and conform to industry or company standards.

Standardization:

- Establish and document CAD standards for naming conventions, layering, dimensioning, and annotation styles.
- Enforce the use of standardized practices across projects to enhance consistency and collaboration.
- Regularly review and update the standards to align with evolving industry practices and requirements.

Collaboration Tools:

- Utilize version control systems or collaboration platforms to manage and track changes in CAD files.
- Implement check-in/check-out procedures to prevent conflicts when multiple team members are working on the same file.
- Use cloud storage or project management tools to facilitate file sharing and communication among team members.

Documentation:

- Maintain comprehensive documentation of libraries, templates, and symbols, including their purpose, usage guidelines, and updates.
- Provide clear instructions or training materials on how to access and utilize these resources effectively.
- Document any customization or modifications made to the standard libraries, templates, or symbols for future reference.

By implementing these practices, you can establish an organized CAD environment that promotes efficiency, consistency, and collaboration among team members. Regular

maintenance and updates to libraries, templates, and symbols will ensure their relevance and usefulness over time.

3.3. Drawing stockholders communication accuracy

When communicating with engineers, design draftspersons, clients, and other stakeholders in the CAD environment, it's crucial to provide progress updates, confirm design requirements, and ensure accurate communication. Here's a guide on how to effectively manage these interactions:

Progress Updates: Regularly communicate with stakeholders to provide updates on the CAD project's progress, Share information on completed tasks, milestones achieved, and any challenges or delays encountered and Use clear and concise language to convey the status of the project, highlighting key achievements and potential issues.

Confirming Design Requirements: Collaborate with engineers, design draftspersons, and clients to understand and confirm the design requirements; it seek clarification on any ambiguous or unclear aspects of the project; Document the agreed-upon design specifications, dimensions, tolerances, and other critical parameters to ensure accuracy.

Attention to Detail: Pay meticulous attention to detail when communicating design-related information; Double-check drawings, specifications, and other documentation for accuracy, completeness, and consistency; Ensure that all stakeholders have a shared understanding of the design details to minimize errors and rework.

Effective Communication: Choose appropriate communication channels for different stakeholders, such as email, phone calls, meetings, or project management tools; Clearly articulate information, using precise language and visual aids when necessary; Actively listen to stakeholders' input, concerns, and suggestions, and respond in a timely and respectful manner.

Documentation: Maintain accurate and up-to-date documentation of all communications with stakeholders; Capture meeting minutes, record decisions made, and document any design

changes or revisions. Use a centralized document management system or project collaboration platform to ensure easy access and retrieval of information.

Collaborative Review Processes: Establish a review process involving stakeholders to verify the accuracy and completeness of CAD drawings and designs; Seek feedback and input from engineers, draftspersons, and clients during the review process; Address any identified issues or discrepancies promptly and document the resolution.

Quality Control: Implement quality control measures to ensure that CAD drawings and designs meet the required standards and specifications; Conduct regular checks for errors, inconsistencies, and compliance with design guidelines; Involve relevant stakeholders in the quality control process to validate the accuracy and completeness of the CAD deliverables.

Professionalism and Interpersonal Skills: Maintain a professional and collaborative demeanor when interacting with stakeholders; Demonstrate strong interpersonal skills, such as active listening, empathy, and effective negotiation, to foster positive relationships; Be responsive, respectful, and open to feedback to create a conducive environment for effective communication.

By following these guidelines, you can effectively liaise with engineers, design draftspersons, clients, and other stakeholders, ensuring accurate communication, confirming design requirements, and providing progress updates in the CAD environment.

Self-Check 3

Instruction: Answer all the following questions

Part I: Choose the correct answer from the give alternatives

1. Which of the following are ways to customize AutoCAD for CNC machining applications?
   A. Creating custom tool libraries and toolpath templates.
   B. Developing custom post-processors for specific CNC machines.
   C. Integrating CAM software with AutoCAD.
   D. Designing custom macros or scripts for automating repetitive tasks.
   E. All of the above.
2. Which of the following are ways to customize SolidWorks for CNC machining applications?
   A. Creating custom machining features and operations.
   B. Developing custom post-processors for specific CNC machines.
   C. Integrating CAM software with SolidWorks.
   D. Designing custom templates and standard parts libraries.
   E. All of the above.
3. Which of the following are commonly used file formats in CAD?
   A. DWG (Drawing)
   B. DXF (Drawing Exchange Format)
   C. STL (Stereolithography)
   D. STEP (Standard for the Exchange of Product Data)
   E. All of the above
4. Which of the following file formats are widely used for 3D printing?

A. STL (Stereolithography)

B. IGES (Initial Graphics Exchange Specification)

C. OBJ (Wavefront Object)

D. AMF (Additive Manufacturing File Format)

E. All of the above

Part II: Machining

Column A	Column B
1. Breaking down complex activities into pieces	A. Key milestones
2. Visual timeline of task start dates, durations, and deadlines	B. Expert judgment
3. Major events, dates, decisions, and deliverables	C. Budget
4. Tools and techniques for estimating activity resources	D. Bottom-up estimating
5. Total allocated budget and any financial constraints	E. Project schedule

Part III: Write short answer for the following questions

1) List at least five of how to effectively manage these interactions?
2) What are the ways you can customize SolidWorks for CNC machines?
3) Write the stages of Project Life Cycle Phases?
4) Write at least three commonly used CAD software platforms?

Operation sheet 3.1

To convert Hewlett-Packard Graphics Language (HPGL) formatted circuit board Computer-Aided Manufacturing (CAM) files into Drawing Exchange Format (DXF) files, you can use a software tool or follow these general steps:

1. Obtain a conversion tool: Look for a software tool that specializes in converting HPGL files to DXF files. There are several third-party tools available that can handle this conversion. Some popular options include ABViewer, GerbView, and UniConvertor.
2. **Install and launch the conversion tool:** Install the chosen conversion tool on your computer and launch it.
3. Open the HPGL file: Within the conversion tool, locate the option to open or import the HPGL file. Select the HPGL file you want to convert.
4. Configure conversion settings (if applicable): Depending on the conversion tool, you may have the opportunity to configure specific conversion settings. For example, you may be able to specify the scale, units, layer names, or other parameters for the resulting DXF file. Adjust these settings as needed based on your requirements.

5. Choose the DXF format: Select the DXF format as the output file format for the conversion process.
6. Start the conversion process: Initiate the conversion by clicking on the "Convert" or similar button within the software tool. The tool will process the HPGL file and generate a DXF file as the output.
7. Save the DXF file: Once the conversion process is complete, specify the location where you want to save the converted DXF file. Provide a name for the file and save it to the desired location on your computer.
8. Review the converted DXF file: Navigate to the location where you saved the DXF file and open it in a DXF-compatible viewer or CAD software. Verify that the converted DXF file contains the desired elements and properties, such as layers, lines, arcs, and other geometric entities.

Operation sheet 3.2

To save or export a drawing in AutoCAD as a Drawing Interchange Format (DXF) file, you can follow these steps:

1. Open the drawing in AutoCAD: Launch AutoCAD and open the drawing file you want to export as a DXF file.
2. Check the drawing units: Before exporting, it's important to ensure that the drawing units are set correctly. Verify that the units in the drawing match the intended scale and units for the DXF file.
3. Choose the "Save As" option: Go to the "File" menu and select "Save As" or use the "Save As" icon on the toolbar.
4. Specify the file name and location: In the "Save Drawing As" dialog box, choose the location where you want to save the DXF file and provide a name for it.
5. Select the DXF file format: In the "Save as type" field or the "Files of type" dropdown menu, choose the DXF format. The available options may vary depending on the version of AutoCAD you are using. Select the appropriate version of DXF based on the compatibility requirements of the target application.

6. Configure the DXF options (if available): Some versions of AutoCAD provide additional options for configuring the DXF export settings. These options may include controlling the version of DXF, selecting the objects to include, specifying layer settings, and controlling the scale. Adjust these settings as needed based on your requirements.
7. Click "Save" to export the DXF file: Once you have specified the file name, location, and options, click the "Save" button to export the drawing as a DXF file. AutoCAD will generate the DXF file based on the specified settings.
8. Review the exported DXF file: After the export process is complete, navigate to the location where you saved the DXF file. Open the file in a DXF-compatible viewer or another CAD software to verify that the drawing has been exported correctly and that the desired elements and properties are preserved.


Operation sheet 3.3

Customizing the CAD-to-CAM workflow involves optimizing the process of transferring designs from Computer-Aided Design (CAD) software to Computer-Aided Manufacturing (CAM) software.

Here are some steps to **customize the CAD-to-CAM workflow**

1. Standardize CAD Modeling Practices:- Standardize naming conventions for CAD files, ensuring consistency and ease of identification during the transfer process.
2. Understand CAM Software Requirements:- Familiarize yourself with the input file formats and requirements of your CAM software.
3. Define Machining Features: Identify and define machining features within the CAD models that are relevant for the CAM software.
4. Create Custom Export Settings: Determine the appropriate file format, such as STEP, IGES, or DWG, based on the CAM software's requirements.
5. Validate and Optimize File Transfer: Adjust export settings or modify CAD models as needed to resolve any discrepancies.

6. Customize Toolpath Generation: Familiarize yourself with the toolpath generation capabilities of the CAM software.
7. Automate CAM Processes:- Utilize scripting or macro capabilities provided by the CAM software to automate repetitive tasks or create custom commands.
8. Establish Documentation and Communication:



Unit Four:- Monitor detail drafting outcomes

This unit is developed to provide you the necessary information regarding the following content coverage and topics:

- Progress Monitoring
- Assisting drafting personnel
- Drawing Validations and documentation
- 3-D models and detail drawings reviewing
- Monitor presentation of drawings and Project outcomes

This unit will also assist you to attain the learning outcomes stated in the cover page. Specifically, upon completion of this learning guide, you will be able to:

- Monitor drafting Progress
- Assist drafting personnel
- Check Drawing Validations and documentation
- Review 3-D models and detail drawings
- Monitor presentation of drawings and Project outcomes

4.1. Progress Monitoring

Monitoring detail drafting outcomes is crucial to ensure accuracy, adherence to standards, and overall quality of the drafted details in a CAD environment.

Progress monitoring is an essential aspect of monitoring detail drafting outcomes in a CAD environment. It involves tracking and assessing the progress of the drafting process to ensure timely completion of tasks and adherence to project timelines. Here are some steps to effectively monitor progress in detail drafting:

Define Milestones and Targets: Break down the detail drafting process into key milestones and targets; clearly define the deliverables and deadlines for each milestone; Establish measurable criteria to determine the completion of each milestone.

Create a Project Schedule: Develop a detailed project schedule that outlines the sequencing and duration of drafting activities; Use project management software or tools to visualize and track the schedule; Allocate resources and assign responsibilities for each task.

Regular Progress Updates: Request regular progress updates from the detail draftspersons; Set up a reporting mechanism to receive timely and accurate information on completed tasks; work in progress, and any challenges or delays encountered.

Track Key Performance Indicators (KPIs): Identify relevant KPIs to measure progress in detail drafting; Common KPIs include the number of completed details, adherence to drafting standards, productivity metrics (e.g., hours spent per detail), and milestone achievement.

Review and Assess Drafting Outputs: Regularly review the drafted details and assess their quality and accuracy; Compare the actual outputs to the established standards and specifications; Identify any issues, errors, or inconsistencies that may require correction or further attention.

Address Bottlenecks and Challenges: Monitor for bottlenecks or challenges that may hinder progress in detail drafting; Identify the root causes of delays or inefficiencies and take appropriate actions to mitigate them; collaborate with the drafting team to troubleshoot issues and implement solutions.

Communication and Collaboration: Foster open and transparent communication with the detail draftspersons; Encourage regular updates and provide a platform for them to share

progress, challenges, and any assistance they may require; Facilitate collaboration among team members to address interdependencies and ensure smooth progress.

Document Changes and Revisions: Document any changes or revisions made during the drafting process. Maintain a record of the reasons for changes, the individuals involved, and the impact on the project schedule. Update the project schedule and communicate revised timelines to stakeholders as necessary.

Conduct Progress Meetings: Organize periodic progress meetings with the drafting team and other relevant stakeholders; Review the overall progress, discuss any issues or concerns, and align on strategies to ensure timely completion; Use these meetings to provide guidance, address questions, and provide feedback on the drafting outcomes.

Adjust and Update the Project Schedule*:* Continuously monitor progress and make necessary adjustments to the project schedule; consider any changes in project scope, resource availability, or external factors that may impact the drafting timeline; Communicate updated schedules to stakeholders to manage expectations.

4.1.1. Common approaches to monitoring project drafting drawing progress

Project drafting drawing progress can be monitored through various methods and tools. Here are some common approaches to monitoring project drafting drawing progress:

a) Task Management Software

Utilize task management software or project management tools that allow you to create tasks for each drawing, assign responsible individuals, set deadlines, and track progress. These tools provide a centralized platform for monitoring the status of each drawing and facilitate collaboration among team members.

b) Gantt Charts

Create a Gantt chart or a visual timeline that illustrates the scheduled start and end dates for each drafting drawing. Update the chart regularly to reflect the actual progress of the drawings. This visual representation helps in monitoring the overall progress and identifying any delays or bottlenecks.




Figure 4.1: Progress monitoring by using Gantt Charts

a) Progress Tracking Sheets

Develop progress tracking sheets or spreadsheets to record the status of each drafting drawing. Include columns for the drawing name, assigned drafter, start and end dates, completion percentage, and any relevant comments or notes. Update the sheet regularly to track progress accurately.

	Project Serial No	Sequential No	Revision	Project Name	Description	Submission Dea
1	D21	D2100012	12	Dahlkemper HQ	First Floor Master Plan	Mar 30, 2020
2	D23	D2300014	14	Dahlkemper HQ	3th Floor Master Plan	Mar 25, 2020
3	A12	A120003	3	Sensation Hotel	Master Plan 2nd Floor	Mar 8, 2020
4	A13	A130002	2	Sensation Hotel	Master Plan 1st Floor	Jan 3, 2020
5	L42	L4200054	54	Lafayette Radio Studio	First Draft of Studio & L...	Jan 9, 2020
6	L43	L4300035	35	Lafayette Radio Studio	Studio Plan	Feb 12, 2020
7	L44	L4400034	34	Lafayette Radio Studio	Lobby	Mar 6, 2020
8	A14	A140004	4	Sensation Hotel	Master Plan Lobby	Dec 13, 2019
9	D22	D2200013	13	Dahlkemper HQ	2nd Floor Master Plan	Apr 15, 2020

Figure 4.2: Progress Monitoring by using Progress Tracking Sheets

a) Regular Reporting

Implement a reporting mechanism where drafters provide regular updates on the completion status of their drawings. This can be done through progress reports, status meetings, or status

emails. Request specific information such as the percentage of completion, any challenges faced, and estimated completion dates.

b) Visual Inspections

Conduct visual inspections or reviews of the drafting drawings at various stages to assess their progress and quality. Compare the actual drawings against the established standards and requirements. Identify any errors, inconsistencies, or areas that require further attention or revision.

c) Communication and Collaboration

Maintain open communication channels with the drafters and other stakeholders involved in the project. Regularly communicate progress updates, discuss challenges, and address any issues or concerns. Encourage collaboration and provide support to ensure smooth progress.

d) Milestone Tracking

Define key milestones or checkpoints in the drafting process and track their completion. Milestones can be significant stages such as conceptual sketches, preliminary drawings, or final revisions. Monitor the progress of each milestone to ensure that the project is progressing as planned.

e) Documentation of Changes

Keep a record of any changes or revisions made to the drafting drawings. Document the reasons for changes, individuals involved, and the impact on the project schedule. This documentation helps in monitoring the progress and provides a historical reference for future analysis.

f) Review Meetings

Conduct regular review meetings with the drafting team and stakeholders to discuss progress, address issues, and provide guidance. These meetings provide an opportunity to align on strategies, address any concerns, and ensure that the project stays on track.

g) Performance Indicators

Define key performance indicators (KPIs) related to drafting drawing progress, such as the number of drawings completed per week, average time taken per drawing, or adherence to project milestones. Monitor these KPIs to assess the overall progress and identify areas for improvement.

By employing these monitoring methods, you can effectively track the progress of project drafting drawings, identify any deviations or challenges, and take proactive measures to ensure timely completion and quality outcomes.

4.2. Assisting drafting personnel

Assisting drafting personnel by supervisors or experts can greatly contribute to the success and efficiency of the drafting process. Here are some ways in which supervisors or experts can provide support and guidance to drafting personnel:

Training and Development

Supervisors or experts can provide training sessions or workshops to enhance the skills and knowledge of drafting personnel. This can include teaching new drafting techniques, software proficiency, industry standards, and best practices. Ongoing professional development ensures that the drafting team stays updated with the latest advancements and improves their overall performance.

Technical Guidance

Drafting supervisors or experts can offer technical guidance and expertise to help drafters overcome challenges or complex design issues. They can provide insights, suggestions, and solutions through one-on-one discussions or regular team meetings. This guidance ensures that the drafting personnel have the necessary support to produce high-quality and accurate drawings.

Review and Feedback

Supervisors or experts can review the drafted drawings and provide constructive feedback to the drafting personnel. This review process helps identify any errors, inconsistencies, or areas for improvement. Feedback can be given verbally or through written comments, highlighting specific areas that need attention or revision.

Quality Assurance

Supervisors or experts can conduct quality assurance checks on the drafting drawings to ensure they meet the required standards and specifications. They can perform detailed inspections, compare the drawings against project requirements, and verify accuracy and completeness. This quality control helps in maintaining consistency and minimizing errors in the final drawings.

Problem-Solving Support

Drafting supervisors or experts can assist drafting personnel in problem-solving by offering their expertise and experience. They can brainstorm solutions, provide alternative approaches, or suggest best practices for overcoming technical challenges or design constraints. This support enables drafters to navigate complex situations and produce optimal results.

Collaboration and Coordination

Supervisors or experts can facilitate collaboration and coordination among drafting personnel. They can encourage knowledge-sharing, promote teamwork, and provide a platform for drafters to discuss challenges, exchange ideas, and learn from each other. This collaborative environment fosters a sense of unity and mutual support within the drafting team.

Resource Allocation

Supervisors or experts can help in efficient resource allocation by assessing the workload, skill sets, and availability of drafting personnel. They can assign tasks based on individual strengths and competencies, ensuring that the right person is assigned to the right task. This optimization of resources maximizes productivity and minimizes potential bottlenecks.

Continuous Improvement

Supervisors or experts can promote a culture of continuous improvement within the drafting team. They can encourage drafters to seek feedback, reflect on their work, and identify areas for growth. Regular performance evaluations and goal-setting sessions can further drive professional development and enhance the overall drafting capabilities.

By providing assistance, guidance, and expertise, supervisors or experts contribute to the development and success of drafting personnel. Their support enhances the quality of drafting outcomes, streamlines the drafting process, and cultivates a skilled and motivated drafting team.

4.3. Drawing validations and documentation

Drawing validations and documentation refer to the process of verifying the accuracy, compliance, and completeness of drawings, as well as creating and maintaining the necessary documentation to support these activities. This process is crucial in various industries, including engineering, architecture, manufacturing, and construction, where precise and reliable drawings are essential for successful project execution.

Drawing validations involve reviewing and evaluating drawings to ensure they meet specific criteria, which can include:

- Accuracy: Verifying that dimensions, measurements, and other specifications in the drawing are correct and aligned with project requirements.
- Compliance: Ensuring that the drawings adhere to relevant industry standards, codes, regulations, and guidelines. This can include safety regulations, project codes, or specific design standards.
- Consistency: Checking that the drawings are consistent with other project documentation, such as specifications, design briefs, or contracts.
- Completeness: Verifying that all necessary information is included in the drawings, such as annotations, labels, symbols, and required details. This ensures that the drawings are comprehensive and provide sufficient information for project implementation.
- Clarity and Legibility: Assessing the clarity and legibility of the drawings to ensure that they can be easily understood by stakeholders, including designers, contractors, and clients.

Drawing documentation involves creating and maintaining records and documentation related to the drawing validation process. This can include:

- Validation Reports: Documenting the findings of the drawing validation process, including identified issues, recommended revisions, and actions taken to address them.
- Revision History: Keeping a record of revisions made to the drawings, including the dates, reasons, and individuals involved in each revision. This establishes an audit trail of changes made over time.
- Approval Sign-Off: Obtaining formal approvals and sign-offs from relevant stakeholders to confirm that the drawings have been reviewed, validated, and approved for use.
- Document Control: Implementing a document control system to manage and track the drawings throughout the validation process. This includes version control, secure storage, and easy retrieval of the validated drawings.

- Organizational Procedures: Documenting the procedures and protocols followed for drawing validations within the organization. This ensures consistency and provides guidance to team members involved in the process.

The purpose of drawing validations and documentation is to ensure the accuracy, compliance, and traceability of drawings, minimize errors and rework, and support effective communication and collaboration among project stakeholders. By following standardized processes and maintaining proper documentation, organizations can enhance the quality of drawings, mitigate risks, and improve overall project outcomes.

4.4. 3-D models and detail drawings reviewing

A 3D model review is a design procedure to present the electronic 3D model to the client to verify that the current stage of the design meets the minimum project requirements for operability, maintainability, constructability, safety, and functionality and that it reflects every discipline's input to the design to date. All discipline engineers review the 3D model through a walkthrough of the plant. Any design changes required are discussed and listed as Model review comments which will be taken care of after the model review.




Figure 4: 3: 3D model and 2d detail drawing

Stages of 3D Model Review

3D Model review, in general, is performed in three stages; 30% model review, 60% model review, and 90% model review. The percentage term used along with model review denoted the percentage completion of the design stage. These model reviews are major checkpoints and

milestones in the engineering design process. Deliverables required from each discipline to achieve each of these checkpoints are defined in the model review matrix.

Typically a model review will not proceed until such time that all of the deliverables required for the specific review have been incorporated. When deliverables are missing for a particular review, the model review may only proceed provided that the associated risks and mitigations have been identified and approved by the project manager.

30% Model Review

A 30% model review means the design is complete by roughly 30% and is the 1st milestone for model preparation. All design data is not yet firm at this stage. This phase aims to lay out the major design elements of the project. It establishes the cost and timeline of the project. 30% model review generates a basis for plant layout, accessibility, and safety measures recommendation. Only the large-diameter critical lines are routed and modeled. At the 30% model review stage, the contractor and client meet to set a basis for further development of the design.

The 30% model review phase is the foundation of the project. From this point onwards the design will be developed further continuously.

60% Model Review

60% Model Review is the second milestone of the model review process and serves the utmost importance of the project. All the doubts raised during the 30% model review are clarified during this phase. In this stage, the team focuses more on the analysis of constructability, budget consideration, modification, and potential issues or concerns. The model review team discusses the constructability of the drawings and any preferred equipment and material needed to build the project during this stage.

90% model Review

This is the final model review and the design is almost final with all data and information. 90% model review finalizes the total design of the model. All the comments from the 60% model review stage are resolved and incorporated into the 90% model review. All drawings and

specifications are ready with the design team for issue as final. 90% model review is the last stage for the client to suggest any minor changes. The project schedule, phasing plan, logistics plan, etc are finalized at this stage.

4.5. Monitoring the presentation of drawings and project outcomes

Monitoring the presentation of drawings and project outcomes involves overseeing and assessing the way drawings are presented and the overall results of a project. This monitoring process helps ensure that drawings are effectively communicated and that project goals and objectives are achieved. Here's an overview of what it entails:

Presentation of Drawings

Clarity and Accuracy: Monitor whether the drawings are presented in a clear and accurate manner, ensuring that the information is easily understandable and free from errors or ambiguities.

Consistency: Check that the drawings are consistent with the project requirements, specifications, and design intent. This includes verifying that all necessary details and annotations are included.

Visual Quality: Assess the visual quality of the drawings, such as the use of appropriate colors, line weights, and graphical representations. Ensure that the drawings are aesthetically pleasing and visually appealing.

Communication and Collaboration:

Stakeholder Engagement: Monitor how the drawings are communicated and presented to various stakeholders, such as clients, contractors, and team members. Evaluate whether the drawings effectively convey the intended information and facilitate understanding and collaboration.

Coordination with Other Disciplines: Assess the integration and coordination of drawings with other disciplines, such as architectural, structural, and mechanical drawings. Ensure that the drawings align with the overall project requirements and fit seamlessly with other components.

Project Outcomes

Quality Assurance: Monitor the overall project outcomes against established quality standards and specifications. Evaluate whether the project deliverables, as reflected in the drawings, meet the required level of quality, functionality, and durability.

Compliance and Regulations: Assess whether the project outcomes, as represented in the drawings, comply with relevant regulations, codes, and industry standards. Ensure that the project adheres to legal and safety requirements.

Timeliness and Efficiency: Monitor the project's progress and completion timeline, comparing it to the projected schedule. Evaluate whether the project outcomes are achieved within the planned timeframe and assess the efficiency of the processes involved.

Cost Control: Monitor project outcomes in terms of budget adherence. Evaluate whether the project is within the allocated budget and assess any cost overruns or savings.

Continuous Improvement

Lessons Learned: Identify and document lessons learned from the project outcomes and the presentation of drawings. This includes capturing insights, successes, challenges, and areas for improvement to inform future projects.

Feedback and Evaluation: Gather feedback from stakeholders regarding the presentation of drawings and project outcomes. This can involve surveys, interviews, or meetings to assess satisfaction levels and identify areas that require attention or improvement.

By monitoring the presentation of drawings and project outcomes, organizations can ensure effective communication, adherence to standards, and successful project completion. It helps identify any issues or deviations early on, allowing for timely corrective actions and continuous improvement throughout the project lifecycle.

Self-Check 3

Instruction: Answer all the question listed bellow

Part I: Choose the correct Answer from the give alternative

1. Which of the following are common approaches to monitoring project drafting drawing progress?
   A. Regular progress reviews and assessments.

B. Comparison against project specifications and requirements.

C. Tracking and documentation of revision history.

D. Communication and collaboration with stakeholders.

E. All of the above.

2. _____visual timeline that illustrates the scheduled start and end dates for each drafting drawing.

A. Gantt Charts

B. Task Management Software

C. Progress Tracking Sheets

D. Regular Reporting

3. Which one not the Presentation of Drawings?

A. Clarity and Accuracy

B. Consistency

C. Visual Quality

D. Stakeholder Engagement

4. Which one is not the stage of 3D Model Review?

A. 30% Model Review

B. 40% Model Review

C. 60% Model Review

D. 90% Model Review

Part II: Matching

Column A	Column B
1. Checking for compliance with industry standards and regulations.	A. Reviewing
2. Assessing the accuracy and completeness of the drawings	B. Evaluating
3. Verifying that the drawings align with project requirements and specifications	C. Ensuring
4. Updating and preserving the records and documentation throughout the drawing validation process.	D. Creating
5. Documenting the details and outcomes of the drawing validation activities	E. Maintaining
6. Generating the initial records and documentation for the drawing validation process.	F. Recording

Part III: Write True if the sentence is correct and write False if it is in Correct

1. Regularly reviewing and assessing the drafted details is an important step in monitoring progress in detail drafting.
2. Documenting and tracking the progress of each drafting task is not necessary for effective monitoring.
3. Comparing the drafted details against the project requirements and specifications is an essential step in monitoring progress.
4. Communicating with the drafting team and addressing any issues or challenges that arise is not important for effective monitoring.
5. Establishing clear milestones and deadlines for each drafting task is not necessary for effective progress monitoring.
6. Tracking the time spent on each drafting task is not relevant for monitoring progress in detail drafting.
7. Monitoring progress in detail drafting does not involve identifying and addressing any quality issues or errors in the drafted details.
8. Regularly documenting and reporting on the progress of detail drafting is not necessary for effective monitoring.

References

1. Jenson,Cecil Howard,Engineering drawing and design,1925,4 th ed.,Macmillan/McGram-Hill
2. Louis Gary Lamit, Descriptive Geometry,1981,1st ed.,Prentice-Hall
3. A text book of engineering drawing, B.Gupta. Nasaka Pashakar publisher
4. UNISDR Monitoring and Evaluation Framework
5. 2008,Textbook of Engineering Drawing, Second Edition
6. http://web.undp.org/evaluation/documents/HandBook/MEHandbook.pdf www.bookspar.com
7. https://www.rishabheng.com/blog/3d-model-review/
8. https://draft.io/example/gantt-chart
9. https://opentextbc.ca/projectmanagement/chapter/chapter-3-the-project-life-cycle-phases-project-management/

Developer's Profile

No	Name	Qualification	Field of Study	Organization/ Institution	Mobile number	E-mail
1)	Abebe Hailiye	(MSc)	Manufacturing engineering	M/G Mulugeta Buli Polytechnic College	0913521369	Aabebe52@gmaile.com
2)	Tsegaye Mulat	(MSc)	Manufacturing technology	A.A tegbaried poly technic college	910411511	Ttshgm97@gmail.com
3)	Boka Terefe	(MSc)	Manufacturing Technology	Ambo poly technic college	917038870	bokaterefe@gmaile.com
4)	Mesay Teshome	BSC	Manufacturing	Hawassa poly technic college	0905 456888	mesayy2018@gmail.com
5)	Mesret Woldemariam	MSC	Manufacturing technology	Wolkite poly technic college	912117416	bmesi2007@gmail.com
6)	Mohammed Bedri	MSC	Manufacturing Technology	Robe poly technic college	913897297	
7)	Mohammed Abdela	MSC	Manufacturing Technology	Ethio italy poly technic college	973794977	mehamed abdela 49@gmail.com